

Addendum



architecture & planning

Date: January 13, 2020 **Addendum No:** 01

Project: South Riverside Park and Shelter 2020
Project No: 2017-0033

Bid Date: January 27th, 2020
Bid Time: 10:00 AM
Bid Place: Waverly City Hall

Total Pages: (1) 8-1/2" x 11" Prints
(2) 11" x 17" Prints (Plan Sheets)

TO ALL HOLDERS OF DRAWINGS AND PROJECT MANUAL:

This addendum is issued to incorporate the following changes in the drawings and project manual. For bids to be considered, this addendum must be acknowledged by so indicating on the Form of Bid. Bidders shall make the following corrections or additions to the bidding documents. These items shall supersede, modify, and/or change all statements or drawings to the contrary in the drawings and project manual and shall take precedence over these documents. Bidders shall base their bid on the drawings and project manual and as modified by the changes herein stated.

GENERAL ITEMS

1. **PRODUCT CLARIFICATION:** Exposed steel indicated to be painted shall use multi-part Epoxy / Acrylic Polyurethane paint system - see attached Sherwin Williams paint system specifications and application instructions.
2. The project is in a rebid phase and some of the previous specification items do not apply ie: stamped concrete.

SPECIFICATIONS:

1. **PRODUCT SPECIFICATION:** Sherwin Williams - Macropoxy 646 Fast Cure Epoxy
2. **PRODUCT SPECIFICATION:** Sherwin Williams - Acrolon 218 Acrylic Polyurethane (Part A - B65-650 Semi-Gloss Series)

DRAWING SHEETS:

1. **Provide missing Sheets A101 and A102**
 - a. Added note to provide schedule 40 pipe conduit runs 36" deep for all buried electrical conduit.
 - b. Changed note for electrical panel @ post to be a 8-slot 70 amp lockable electrical box.

PRODUCT APPROVALS:

Contingent upon strict compliance with the drawings and specification, all product approvals listed herein are approved as if certified in writing by the product supplier/installer to be equal to or better in every significant respect to that required by the plans and specifications and that it will perform adequately in the application indicated and as intended. If such approved products do not meet these requirements, the supplier/installer shall be responsible for making adjustments acceptable to the Architect to meet the requirements of the contract documents.

1. APPROVED SUBSTITUTE: LANDSCAPE TRANSFORMER
 - a. Kichler - Pro Series Transformer Stainless Steel (Wattage as required) (Model # 15PR300SS)
2. APPROVED SUBSTITUTE: BRICK PAVERS
 - a. Yankee Hill Brick & Tile - 4 x 8 x 2-1/4 Paver - Medium ironspot
3. APPROVED SUBSTITUTE: (07 41 13) Metal Roof Panels
 - a. McElroy Metal / Max Rib Ultra / 26ga / Kynar 500 finish (Approved substitute for Metal Sales / Pro-Panel II)

ATTACHMENTS:

3. **ADDED DRAWING SHEETS:** A101,A102

Respectfully Submitted,
Align Architecture & Planning, PLC